# BRUHAT BANGALORE MAHANAGARA PALIKE

## Name of Works : Providing Gallery to Musical Fountain in JP Park in Ward No 17, J P Park.

## Rate Analysis ERIL

CSR: 2018-19

| Sl No | Description of work | Unit | Page No. | Item No. | Basic Rate | Total | AW 6% | Sub Total | TP 4.74 % | Grand Total |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. | Cum | 13 | 4.2 | 5650.24 | 5650.24 | 339.01 | 5989.25 | 283.89 | 6273.14 |
| 2 | KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. TMT bars Fe 550 | Tonne | 18 | 4.46.3 | 87969.00 | 87969.00 | 5278.14 | 93247.14 | 4419.91 | 97667.05 |

Scanned with CamScanner